

Addendum #2

RFP #81010-17-03

September 5, 2017

This addendum will answer any questions that have been asked as of September 1, 2017.

1- We only see 2 DI-3C, L=8' Curb Inlets on the plans. The Bid Item sheet shows a total of 5 structures, (2 DI 3B, 2 DI-3C and 1 Drop Inlet DI-7) – can you confirm the throat lengths on structures 12 & 14.

The throat length for the DI-3C structures is listed incorrectly on page 16 of the bid proposal. The correct length for both of the DI-3C structures is eight feet (8').

2- Can you confirm the height and pipe size of the DI-7 you have listed below – we don't see it on the plans.

The 2 DI-3B structures, the DI-7 structure (and associated piping), and the EW-12 structures are on the set of plans for the portion of the roadway from STA 10+76.60 to 17+77.56.

3- EW-12s you show below – can you confirm the slope – 2:1, 3:1 or 4:1 – Please Advise.

Since the two projects are being constructed together, it is not anticipated that the EW-12's will need to be installed. For unit pricing purposes, please specify 4:1 for the slope.